

PRICE SCHEDULE

Replacing of sanitary fittings, supply and fixing new sanitary fittings, painting to the walls in the Managing Director's rest room, Removing supply and fixing new floor tiles in front of the portico, servicing and replacing the specials and fixing new storage tank in the pressure pump and painting the walls, supply and fixing false ceiling, painting to the walls in certain areas in sugar Federation AT AAVIN ILLAM BUILDING, NANDANAM, CHENNAI - 35

ABSTRACT

S.No	Quantity		Description of work	Unit	Rate	Amount
1	1.00	Nos	Supplying and fixing of 15 mm two way BIP COCK including labour charges, etc complete as directed by the federation engineers and as per standard specification (Brand - Jaquar or Equivalent)	Each		
2	2.00	Nos	Supplying and fixing of 3/4 ' ANGLE COCK including labour charges, etc complete as directed by the federation engineers and as per standard specification. (Brand - Jaquar or Equivalent)	Each		
3	1.00	Nos	Supplying and fixing of PILLAR COCK including labour charges, etc complete as directed by the federation engineers and as per standard specification. (Brand - Jaquar or Equivalent)	Each		
4	1.00	Nos	Supplying and fixing of HEALTH FAUCET including labour charges, etc complete as directed by the federation engineers and as per standard specification. (Brand - Jaquar or Equivalent)	Each		
5	1.00	Nos	Supplying and fixing of 3 Pin hook including labour charges, etc complete as directed by the federation engineers and as per standard specification. (Brand - Jaquar or Equivalent)	Each		
6	1.00	Nos	Supplying and fixing of Towel rail including labour charges, etc complete as directed by the federation engineers and as per standard specification. (Brand - Jaquar or Equivalent)	Each		
7	2.00	Nos	Supplying and fixing of Flush control panel including labour charges, etc complete as directed by the federation engineers and as per standard specification. (Brand - Jaquar or Equivalent)	Each		
8	6.00	Sqm	Dismantling the removal of debris and spread as shown by the Federation Engineers and Paving the floor with pre-polished concrete anti-skid tiles 300 mm x 300 mm (Required shape and design) of 20mm thick of approved quality and colour laid in Cement Mortar 1:3 (One Cement and Three sand) 20mm thick and pointed with white cement mixed with colouring pigment at the rate of 0.40 Kg. / sq.m., curing, etc., and complete complying with standard specification and as directed by the departmental officers.	Sqm		

S.No	Quantity		Description of work	Unit	Rate	Amount
9	51.50	Sqm	Painting the wall surface using best quality of PLASTIC Emulsion paint TWO COAT as per the Specification of the approved colour to give an even shade, including cost of brushes and all other materials required and scaffolding charges.	Sqm		
10	39.50	Sqm	Painting the old surface using best quality of Damp proof paint one COAT as per the Specification including cost of brushes and all other materials required and scaffolding charges.	Sqm		
11	1.00	Lot	Providing casing pipe for AC wire etc complete.,	Lot		
12	16.00	sqm	Supply and fabricating ,erecting and fixing Hilux (or) Equivalent board false ceiling upto a ceiling height of 4.5 m from floor level and replacing the own out aluminium channels etc complete as directed by the Federation officers	sqm		
13	1.00	Lot	Service the Pressure Pump including replacing mechanical parts such as re- winding , Gas cutting,Water seall, Bearing,shaft and impaller and replace the new Pressure tank (24 Litre capacity) etc Complete as directed	Lot		
			Total			
			GST 18 %			
			Total			

Signature of the contractor