

<b><u>PRICE SCHEDULE</u></b>
------------------------------

From :  
The Managing Director,  
TCMPF Limited ,  
Nandanam ,  
Chennai-35

To :

**Name of Work: Repairing and replacing the damaged generator shed at DMPDD office campus, MMC, Chennai - 51.**

Sl.no	Qty	Description	Rate	unit	Amount
1	1.00	Dismantling and removing the existing roof sheet and purlin etc complete as directed by the federation officers		Sqm	
2	30.00	Supplying and fixing in position of Powder coated galvalume colour sheet of 0.47mm thickness with necessary bolts, nuts and washers, metal screws etc. complete with standard specification and as directed by the departmental officers. The galvalume sheet make should be of Jindal, TATA, JSW or equivalent make.		Sqm	
3	165.00	fabricating, Supplying and fixing in position of Truss work Mild Steel angle and Mild steel flat & fixing purlin M.S Channel including cutting, welding & dismantling RCC / brick wall same redoing as per original position of wall etc., including Primer and enamel one coat, completed as directed by the departmental officers.		Kg	
4	30.00	Providing granolithic floor finish of the following thickness with plain cement concrete 1:2:4 (One Cement, Two sand and Four aggregate) using 10 to 12mm gauge hard broken stone jelly including laying, finishing and the top rubbed smooth with power trawl, thread lining, curing etc. complete complying with standard specification and as directed by the departmental officers. (The rate is inclusive of necessary planking for panelling wherever necessary and as directed by the departmental officers)		Sqm	
5	0.20	Plain Cement Concrete 1:2:4 (one cement, two m-sand and four hard broken stone jelly) using 20mm jelly for the machinery bed and other bed blocks works and flooring including curing (excluding centering) etc., complete as per standard specifications and as directed by the departmental officers.		Cum	
6	6.00	Plastering with Cement Mortar 1:5 (One cement and Five m-sand), 12mm thick in all floors including scaffolding neatly finishing, curing etc. complete complying with standard specification and as directed by the departmental officers.		Sqm	

Sl.no	Qty	Description	Rate	unit	Amount
7	10.00	Supplying and painting two coats of newly plastered wall surface with ready mixed plastic emulsion paint (exterior) of first class quality and of approved color over one coat of priming coat including priming coat and also make good of the surface with sand paper, putty, scaffolding etc., complete as directed by the departmental officers.		Sqm	
8	4.00	Supplying and erecting steel centering including necessary supports for plane surfaces for Reinforced Cement Concrete works such as column footings, column pedestals, plinth beams, grade beams, staircase steps, etc. which require only nominal strutting using mild steel sheets of size 90cm x 60cm and 10 BG stiffened with welded mild steel angles of size 25mm x 25mm x 3 mm for boarding, laid over silver oak joists of size 10cm x 6.5cm spaced at about 75cm Centre to Centre or at suitable intervals etc. complete in all floors complying with standard specification. (Payment for centering shall be given after the concrete is laid- Upto Basement - Plain surface		Sqm	
9	16.00	Painting new iron works such as steel doors, windows, ventilators, window bars, balustrades etc., with two coats of best approved first quality and colour of synthetic enamel paint over the existing red oxide priming coat in all floors excluding cost of priming coat etc., complete as directed by the departmental officials.		Sqm	
		Sub Total			
		GST -18 %			
		Total			

Signature of the Contractor